

ORDINANCE NO. 466

AN ORDINANCE TO AMEND ORDINANCE NUMBER 446, RELATING TO SANITARY SEWER PIPE SPECIFICATIONS AND DECLARING AN EMERGENCY.

THE CITY OF STAYTON ORDAINS AS FOLLOWS:

SECTION 1.

Page III-5, Section B. Materials, Subsection 2 Sewer Pipe of Ordinance No. 446, entitled "An Ordinance adopting standard specifications for Public Works construction within the City of Stayton" shall be henceforth amended to include the following:

d. Poly-Vinyl-Chloride (PVC) Gravity Sewer Pipe

1. Conform to ASTM D3034 SDR 35 bell and spigot with rubber gasket type joints.
2. Joints to conform to ASTM D3212.
3. Couplings-"Ring-Tite" or Fluid-Tite", manufactured by John-Manville or Certain Teed or equivalent.

e. Acrylonitrile-Butadiene Styrene (ABS) Sewer Pipe

1. 8-inch and larger pipe to be ASB Composite sewer pipe conforming to ASTM D2680 with solvent cemented joints (Type SC).
2. 4-inch and 6-inch pipe to be solid wall ABS pipe conforming to the following specification (which exceeds ASTM D2751). Joints to be solvent cemented:

a) ABS solid wall side sewer pipe & fittings to be manufactured from resins described in paragraph 5.1 of D2680 and tested in accordance with paragraph 9.3 of D2680 to the following limits:

<u>Diameter</u> <u>(in.)</u>	<u>Type</u>	<u>Wall</u> <u>(ins.)</u>	<u>F/Y</u> <u>(psi)</u>	<u>Failure Deflection</u> <u>(%)</u>
4"	ES	0.190	150	15
6"	ES	0.280	150	15

3. Primer & cement to conform to paragraph 5.4 of ASTM D2680.

SECTION II.


It is hereby adjudged and decreed that the existing conditions are such that this Ordinance is necessary for the immediate preservation of the public peace, health, and safety of the City of Stayton, and an emergency is hereby declared to exist, and this Ordinance shall take effect and be in full force from and after its passage.

PASSED by the Common Council on this 30 day of August, 1976.

APPROVED by the Mayor this 31 day of August, 1976.


MAYOR

ATTEST:


RECORDER